## Seaward Hand-Held Appliance Tester

## **Product Images**



## **Description**



- Performs safety checks on Class I and II equipment
- Compares results of insulation and earth continuity checks against factory set pass levels
- A simple go/no go checker
- Supplied with robust carrying case
- Insulation Test: 500V DC  $\pm$  at an insulation level of 2m $\Omega$  at rated mains supply, pass level 2m $\Omega$
- Earth Continuity Test: Test current up to 25A AC, pass level  $0.25\Omega$