

Seaward Hand-Held Appliance Tester

Product Images



Description



Production Equipment Europe
Superior Service – Single Source

- Performs safety checks on Class I and II equipment
- Compares results of insulation and earth continuity checks against factory set pass levels
- A simple go/no go checker
- Supplied with robust carrying case
- Insulation Test: 500V DC \pm at an insulation level of 2m Ω at rated mains supply, pass level 2m Ω
- Earth Continuity Test: Test current up to 25A AC, pass level 0.25 Ω